



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CSR/082	
HUNAIID CONSTRUCTION			Our Enquiry Date		2026-01-17	
9 jamali manzil, near sharafi marriage hall,, Behind apsara skyline,			Vendor Ref. No		01	
pratapnagar road			Vendor Ref. Date		2026-01-21 16:30:00	
City: vadodara Pin: 390004 State: Gujarat			Project No: UWB/2025-26/CSR/039 Project Name: <i>Need for Renovation and Refurbishment of the center- Vikas Jyot Trust</i>			
Contact Person: Hunaid Kasimi Mobile: 7984649263						
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	P & L Brickwork using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in superstructure in Cement Mortar 1:6 (1- Cement : 6 - fine sand) (NA)	Cubic	0.5	16,000.0	18.0	9,440.0
2	Providing 12 mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor two level and finished even and smooth in Cement mortar 1:3 (NA)	Square	3.0	750.0	18.0	2,655.0
3	Providing and laying polished (both sides) kota stone slab 25mm thick in cupboard shelves fixing wall with proper groove and fixing with cement etc. (NA)	Square	9.1	550.0	18.0	5,912.4
4	Providing and applying two coats of washable interior emulsion paint including priming coat of following brand on surfaces to give an even shade including finishing and thinning as per manufacturer's specification after thoroughly cleaning the surface free from mortar droppings and other foreign matter. Item includes very minor touching with lapi whenever required, making the surface even and smooth by sand papers. 1. Asian Paint : Premium Emulsion 2. Nerolac Paint : Lotus Touch 3. ICI Dulux (Akzo Nobel) : ICI Dulux 3 in 1 4. Berger Paint : Easy Clean 5. GROWEL : Super Acroplast Plastic Emulsion Paint (NA)	Square	245.4	270.0	18.0	78,168.5
5	Providing and applying two coats of synthetic enamel paint (oil paint) (excluding priming coat) on new / existing structural steel and other metal surface of following brand and make 1. Asian Paint : Apcolite 2. Nerolac Paint : Nerolac Synthetic 3. ICI Dulux (Akzo Nobel) : Dulux Gloss 4. Berger Paint : Luxol High Gloss 5. GROWEL Paint : Pentolite Super Synthetic enamel (NA)	Square	56.9	350.0	18.0	23,491.4
6	Providing and fixing two track aluminum shutters with frame for storage unit in hall, aluminum partition for beauty parlour section with door having extruded aluminum colour anodized section with bakelite sheet etc. complete (NA)	Square	22.0	5,500.0	18.0	1,42,844.9
7	Minor repairing to windows, doors, ventilators etc such as replacement of hinge, handle, stopper (if found not working), minir repairing etc. to make them in smooth working condition. (NA)	Nos	9.0	900.0	18.0	9,558.0
8	Providing and fixing a stainless steel mosquito net to the grill and the window ventilation (NA)	Square	8.1	600.0	18.0	5,727.7
9	MS Steel work for grill door from various steel section including cutting, hoisting, fixing in position and applying a priming coat of red lead paint (NA)	Kgs	50.0	200.0	18.0	11,800.0
10	Providing & laying 24" x 24" vitrified 8 mm thick tile flooring fixing on existing flooring by adhesive material jointed with colour cement slurry cleaning the surface etc. complete for antiskit. (NA)	Square	97.2	1,300.0	18.0	1,49,043.4
11	Painting the inside walls of classrooms as well as outside passage walls with mural painting as per given design (NA)	Square	150.0	2,100.0	18.0	3,71,700.0
12	Providing and fixing Branding Name Plate on black granite with Golden letters (plate size 2'0" x 1'6") with installation (NA)	Nos	1.0	7,500.0	18.0	8,850.0
13	Electrical Work : Providing and fixing of following electrical items -switch boards-2 no., 48" celeing fans - 3no., LED tube light -1 no. and misc if any etc. complete (NA)	Job	1.0	18,000.0	18.0	21,240.0
			Quotation Value			8,40,431.0
Payment Terms		within 7 days after completion				
Freight		inclusive				
Installation		inclusive				
Delivery Schedule		45 days				
Warranty/Guarantee		1 year after completion				
General Remarks		any change has to be informed while work is in progress				

Print Date/Time: 2026-01-21/16:30:58