



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CSR/066	
NAV PRODUCTS			Our Enquiry Date		2025-12-23	
987 6 1 GIDC ESTATE MAKARPURA			Vendor Ref. No		NAV PRODUCTS	
VADODARA			Vendor Ref. Date		2025-12-31 11:44:00	
City: Vadodara Pin: 390010 State: Gujarat			Project No: UWB/2025-26/CSR/034 Project Name: <i>Water ATM Panoli and Bakrol</i>			
Contact Person: NAV PRODUCTS Mobile: 9662048411						
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	250 LPH RO Unit with 3-year AMC • Capacity: 250 LPH • ISI Marked, ISO Certified • FSSAI & BIS Approved Kent / Eureka Forbes / Blue Star / AquaSure / Livpure / Zero B / Netsol Water Or Equivalent (Panoli and Bakrol)	Nos	2.0	1,80,000.0	18.0	4,24,800.0
2	2 Ton Chiller • Steel frame, copper condenser & evaporator • Corrosion-resistant & permitted material • Eco-friendly refrigerant • Certifications: ISI, CE, NSF Blue Star / Voltas / Celfrost / Western / Usha Or Equivalent (Panoli and Bakrol)	Nos	2.0	1,15,000.0	18.0	2,71,400.0
3	3-Layer Antimicrobial Raw Water Storage Tank – 2000 Ltr. • Triple-layer, food-grade polymer • Anti-bacterial (silver-ion coating) 3 Layer Antimicrobial Raw Water Storage Tank Certified Food Grade and Anti-Microbial Storage (Bakrol)	Nos	1.0	20,000.0	18.0	23,600.0
4	Water Purifier Storage Tank (1000 Litre – 3 Layer with M.S stand instrument) • Triple-layer, food-grade polymer • Anti-bacterial (silver-ion coating) 3 Layer Antimicrobial Raw Water Storage Tank Certified Food Grade and Anti-Microbial Storage (Panoli and Bakrol)	Nos	2.0	10,000.0	18.0	23,600.0
5	GSM Base Coin Panel (1 Pair) ISI Marked, Standard (Panoli and Bakrol)	Nos	2.0	48,000.0	18.0	1,13,280.0
6	Earthing and all necessary electrical fitting • Anchor Cables, MCB, Switchboards (ISI Marked) • Complete earthing & wiring Standard ISI Approved Or Equivalent (Panoli and Bakrol)	Job	2.0	21,000.0	18.0	49,560.0
7	Fully Automated Plant Assembly • Lubi Motors • SV Valves • Finolex UPVC Pipes Lubi / Finolex / Equivalent Or Equivalent (Panoli and Bakrol)	Job	2.0	42,000.0	18.0	99,120.0
8	Renovation of the 10x10 feet old structure for set up of water ATM with kota stone, painting, mural painting for branding with plumbing for waste water drainage line and raw water stand etc. (Bakrol)	Job	1.0	85,000.0	18.0	1,00,300.0
9	Fixing of 1.5 HP motor pump, with pipe, starter and wire and its automatization and plumbing of water supply line and waste water line • Pump: 1.5 HP (Lubi or equivalent) Water supply line from overhead water tank to the water tank may be included in this item (pipes of Supreme, Astral etc.) Lubi / Equivalent (Panoli)	Job	1.0	48,000.0	18.0	56,640.0
10	CCTV Camera (HD) • 2 MP HD Resolution • Night Vision, Bullet Camera • SIM-based operation Canon / Dahua / CP Plus / Ahuja / Samsung / Hikvision Or Equivalent (Panoli and Bakrol)	Nos	2.0	11,000.0	18.0	25,960.0
11	Civil Work Construction 12’ x 12’ plinth platform for prefab shed (c/o) upto plinth level. as per drawing. Height of the platform 2’ above surrounding ground level. Proper drainage system with outlet. Separate pedestal of 1600 mm dia (as per drawing) (Panoli)	Nos	1.0	1,05,000.0	18.0	1,23,900.0
12	Comprehensive Maintenance Contract (CMC) • 2 Years (after 1-year brand warranty) (Panoli and Bakrol)	Nos	2.0	49,000.0	18.0	1,15,640.0
13	Cabinet Unit for Water ATM Machinery • Dimensions: 12’ x 12’ • 50 mm PUF insulated cabinet • Door size: 6’ x 3’ (Panoli)	Nos	1.0	2,20,000.0	18.0	2,59,600.0
14	Monitoring & Evaluation (Monthly Monitoring Report, Key Outputs and other associated details will be shared regularly) (Panoli and Bakrol)	Nos	2.0	18,000.0	18.0	42,480.0
15	Transport, Installation, Training (Panoli and Bakrol)	Nos	2.0	6,000.0	18.0	14,160.0
16	Sim cards with 3 Years of Data Plan (Panoli and Bakrol)	Nos	4.0	15,000.0	18.0	70,800.0
			Quotation Value			18,14,840.0
Payment Terms		50% ADVANCE 30% AFTER CIVIL AND 20% POST INSTALLATION				
Freight		INCLUDED				
Installation		AT SITE				

Delivery Schedule	8 to 10 Weeks
Warranty/Guarantee	AS PER QUOTATION
General Remarks	NONE

Print Date/Time: 2025-12-31/11:44:10