



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CSR/080	
SHREE HARI Engineering			Our Enquiry Date		2026-01-17	
40, RASHMI GROWTH IND HUB NR, GRANDVISHLA IND EST.			Vendor Ref. No		VRC/00264	
ODHAV CIRCLR AHMEDABAD			Vendor Ref. Date		2026-01-20 12:21:00	
City: AHMEDABAD Pin: 382415 State: GUJARAT			Project No: UWB/2025-26/CSR/036 Project Name: <i>Nayi Peהל – From Hygiene to Hope: Pilot Project on Sanitary Napkin Manufacturing Unit</i>			
Contact Person: SUNIL KUMAR Mobile: 8000801504						
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	Sanitary Pad Machine - Aluminum Structure Design. The machine can work with five input rolls of size 180 to 200 mm, Using Non-Woven and Melt-Blown Fabrics with a minimum thickness of 20 GSM and a maximum thickness of 35 GSM. Product per minute Min 30 to Max 35 minutes, Machine weight: 170 kg. approx. Dimension of Machine: 3300mm L * 650mm W* 1800mmh Approximate. Electrical Power: Single Phase, Motor with Control Panel and Frequency. drive with Motor. Ultrasonic Welder: 15k, 1800Walt 1 Nos. (NA)	Nos	1.0	10,90,000.0	18.0	12,86,200.0
2	UV BOX Machine for Sterilization: 16*16*16 Inch, M.S.Powder Coting, Timer Control, Trays 2 Nos, Timer: Digital Meter, 11W * 02 Number (NA)	Nos	1.0	52,000.0	18.0	61,360.0
3	Sealing Machine for final packet sealing: Supply Voltage: 220V 50-60HZ, Overall Power: 750W, Sealing Width: 14MM, Sealing Speed: 0-16M/Minute, Delivery Load: 6 Kg. (NA)	Nos	1.0	40,000.0	18.0	47,200.0
4	XXL Die for Pads Custom tooling sealing: 320MM Pad size and XXL Size, Die Roller, Embossing and Cutting Aer Separate Material D2 and Hardness: 58 HRC (NA)	Nos	1.0	98,000.0	18.0	1,15,640.0
5	Branding and Packaging Design Logo, pouch, design setup: 4.5*13 Size With Gadhate Max 4 Colour Printing (NA)	Kgs	300.0	240.0	18.0	84,960.0
			Quotation Value			15,95,360.0
Payment Terms		50% ADVANCE WITH PO AND 50% BEFORE DISPATCH				
Freight		32000/ TRANSPORATION COST A.BAD TO ABARODA				
Installation		INSTALLATION CHARGES 23000/ AMOUNT				
Delivery Schedule		1 MONTH DELIVERY WITHIN PO ORDER DATE				
Warranty/Guarantee		machinery is warranted against any manufacturing defects for a period of 1 years from the date it is said to be ready for shipment - ELECTRONICS PARTS AND ULTRASONIC DEVICE AND DIE ROLLER WARRANTY AND GAURANTY IS NOT INCLUDE.				
General Remarks		VISTING CHARGES FOR ANY PROBLEM APID AMOUNT 4000/- BY CUSTOMER FOR ALL VISIT BY OUR PERSON				

Print Date/Time: 2026-01-20/12:21:27