



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CSR/073	
Kelivan Landscapes			Our Enquiry Date		2026-01-07	
406, Phonix Avenue, Opp BRG farm,			Vendor Ref. No		KL/042/25-26	
Sama Savli Road, Vadodara			Vendor Ref. Date		2026-01-12 14:21:00	
City: Vadodara Pin: 390021 State: Gujarat			Project No: UWB/2025-26/CSR/038 Project Name: <i>Urban Forest Development through Miyawaki Technique at Tarsali STP Plant</i>			
Contact Person: Amruta Kulkarni Mobile: 9820798617						
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	3000 Plants of Trees (Plantation of Trees • Saplings of 2 ft. to 5 ft. height (Including 40-45 native tree species) • Planting as per Miyawaki Technique (grid system). (NA)	Nos	3,000.0	80.0	18.0	2,83,200.0
2	Drip Irrigation, Brand Name: Netafim, Size: 16mm. complete drip irrigation system at entire plantation (NA)	Square Feet	15,000.0	20.0	18.0	3,54,000.0
3	Land Preparation- Desilting of land up to 3 f.t. (NA)	Square Meter	2,500.0	200.0	18.0	5,90,000.0
4	Mulching and Manure (NA)	Kgs	15,000.0	15.0	18.0	2,65,500.0
5	Manpower for Digging Pitts for Plantation (NA)	Nos	10.0	5,000.0	18.0	59,000.0
6	Bricks- 1.5 Mtrs Wide pathway through bricks, including installation work (NA)	Nos	1,500.0	110.0	18.0	1,94,700.0
7	Bamboo Stick for Plant Support (NA)	Nos	3,000.0	5.0	0.0	15,000.0
8	Woven Chain Link Fencing for a plantation area. (NA)	Running Foot	750.0	170.0	18.0	1,50,450.0
9	Iron Gate (8 ft * 6 ft) 84 sq. ft. Made from an iron pipe of 5 mm with Supply and Installation. (NA)	Nos	1.0	25,000.0	18.0	29,500.0
10	Branding Wall & Plaque (• Brick masonry with plaster (44 sq. ft.) • ACP sheet plaque on brick masonry (12 sq. ft.) • Color work (400 sq. ft.) (NA)	Nos	1.0	65,000.0	18.0	76,700.0
11	Maintenance Contract for 2 Months February 2026 to March-2026 Scope includes: 1) Replacement of plants 2) Regular watering 3) Deweeding 4) Ensuring proper soil cover 5) Daily visit by a gardener 6) Monthly progress report 7) Any other activity as required. (NA)	Months	2.0	12,000.0	18.0	28,320.0
			Quotation Value			20,46,370.0
Payment Terms		30% Advance , 50% against material, 20 % after work completion				
Freight		included				
Installation		within 30 days				
Delivery Schedule		after 15 days of PO				
Warranty/Guarantee		any animal damage will be charge extra for mortality				
General Remarks		Providing basic water facility points and electric points under client scope				

Print Date/Time: 2026-01-12/14:21:35