



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CIC/015	
Excel Infrastructure			Our Enquiry Date		2026-01-19	
C-127 BHAVNAPARK SOCIETY			Vendor Ref. No		UWB/ Don Bosco	
Nr Amit Nagar , Sama Savli Road			Vendor Ref. Date		2026-01-19 18:01:00	
City: VADODARA Pin: 390022 State: GUJARAT			Project No: UWB/2025-26/CIC/006			
Contact Person: Samir Patel Mobile: 9724656815			Project Name: Renovation of Don Bosco Snehalaya			
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	Cleaning the terrace (Cleaning the terrace with wire brush, washing the terrace and Providing and Applying Chemical Water proofing Of SikaMake Water proofing chemical application with 05 Years of water leakage guarantee)	Square Feet	279.9	675.0	18.0	2,22,940.4
2	Demolition of Brick Masonry (Demolition of Brick Masonry Demolition of existing brick masonry, including stacking of serviceable materials and disposal of unserviceable materials with all leads and lifts, complete.)	Cubic Meter	1.7	3,500.0	18.0	7,021.0
3	MS Railing at Terrace with color (NA)	Square	120.0	325.0	18.0	46,020.0
4	Interior Paint Work (Providing & Applying Interior Washable Emulsion PaintProviding and applying two coats of washable interior emulsion paint of approved brand over one coat of primer on internal plastered surfaces. Work includes cleaning the surface free from mortar droppings, sandpapering, minor touching with putty (lapi) wherever required, and finishing as per manufacturer’s specifications. Asian Paints: Premium Emulsion)	Square Feet	87.7	250.0	18.0	25,871.5
5	Exterior Paint Work (Providing & Applying Exterior Premium Emulsion PaintProviding and applying two coats of exterior premium emulsion paint of approved brand over one coat of primer on existing plastered surfaces, including finishing, thinning as per manufacturer’s specifications, and providing necessary scaffolding, jhoolas, etc., complete as directed by E.I.C. Asian Paints: Apex Ultima)	Square Feet	96.8	250.0	18.0	28,556.0
6	Polythene Pipes (Providing and Fixing Polythene Pipes (110 mm Dia)Providing and fixing low-density polythene pipes of 110 mm diameter, 10.0 kgf/cm² working pressure, complete with special flange/compression-type fittings, wall clips, etc., including making good the damaged wall, ceiling, and floor surfaces, complete.)	Running Feet	30.0	750.0	18.0	26,550.0
7	Plumbing Work (Plumbing Labour Charges for Shifting PVC LinesLabour charges for plumber for removing the existing water supply PVC lines on the terrace during waterproofing work and refitting them after completion, including all required materials, complete.)	Job	1.0	10,000.0	18.0	11,800.0
8	Crackseal Work (Opening the hair crack and Filling Cracks in wall / Old brick bat water proofing and filling it with Asian / Sika make crack filling agent (Crackseal))	Meters	150.0	250.0	18.0	44,250.0
			Quotation Value			4,13,009.0
Payment Terms		70% Advance 30% after completion of Work				
Freight		Included				
Installation		Included				
Delivery Schedule		35 Days after work order				
Warranty/Guarantee		5 Years for Water proofing				
General Remarks		Water and Power to be provided Free of Cost				

Print Date/Time: 2026-01-19/18:01:52