



UNITED WAY OF BARODA

Ground Floor, Office No. 5,1965 Alembic City Avenue, Near Alembic House, Alembic Road, Vadodara - 390 003(Gujarat) INDIA.

Supplier/Vendor			Our Enquiry No		UWB/2025-26/CIC/011	
Suril Construction			Our Enquiry Date		2025-12-15	
114,Mahavir industrial estate			Vendor Ref. No		VRC/00091	
Karelibaug			Vendor Ref. Date		2025-12-20 16:45:00	
City: Vadodara Pin: 390018 State: Gujarat			Project No: UWB/2025-26/CIC/006 Project Name: Renovation of Don Bosco Snehalaya			
Contact Person: Irin patel Mobile: 8511101260						
Srl	Item Particulars	UOM	Qty	Unit Rate	G.S.T %	Value
1	Demolition of Existing Terrace Waterproofing (Demolition of existing terrace waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all leads and lifts, complete.)	Sq	279.9	225.0	18.0	74,308.1
2	Demolition of Brick Masonry (Demolition of existing brick masonry, including stacking of serviceable materials and disposal of unserviceable materials with all leads and lifts, complete.)	CUMT	1.7	2,500.0	18.0	5,044.5
3	Providing Waterproofing Treatment on Terrace (Providing and applying waterproofing treatment on the terrace at any level using brickbat coba of average 150 mm thickness in cement mortar 1:3, mixed with approved waterproofing chemicals. The top surface shall be finished with China mosaic tiles fixed in white cement, with proper slope, including all materials, labour, and tools, complete as per standard specifications.)	Sq	279.9	1,490.0	18.0	4,92,085.0
4	Providing and Laying Half-Brick Masonry (Providing and laying half-brick masonry in common burnt clay bricks having a crushing strength not less than 35 kg/sq.cm, in cement mortar 1:4 (1-cement : 4-coarse sand), complete.)	Sq	18.6	1,375.0	18.0	30,162.3
5	Providing 15 mm Thick Cement Plaster (Providing 15 mm thick cement plaster in a single coat on brick or concrete walls for interior plastering up to floor two level, finished smooth and even in cement mortar 1:3, complete.)	Sq	96.8	575.0	18.0	65,672.0
6	Providing & Applying Interior Washable Emulsion Paint (Providing and applying two coats of washable interior emulsion paint of approved brand over one coat of primer on internal plastered surfaces. Work includes cleaning the surface free from mortar droppings, sandpapering, minor touching with putty (lapi) wherever required, and finishing as per manufacturer's specifications. Asian Paints: Premium Emulsion)	Sq	87.7	230.0	18.0	23,809.9
7	Providing & Applying Exterior Premium Emulsion Paint (Providing and applying two coats of exterior premium emulsion paint of approved brand over one coat of primer on existing plastered surfaces, including finishing, thinning as per manufacturer's specifications, and providing necessary scaffolding, jhoolas, etc., complete as directed by E.I.C. Asian Paints: Apex Ultima)	Sq	96.8	250.0	18.0	28,553.1
8	Providing and Fixing Polythene Pipes (110 mm Dia) (Providing and fixing low-density polythene pipes of 110 mm diameter, 10.0 kgf/cm² working pressure, complete with special flange/compression-type fittings, wall clips, etc., including making good the damaged wall, ceiling, and floor surfaces, complete.)	RMT	32.0	675.0	18.0	25,496.0
9	Plumbing Labour Charges for Shifting PVC Lines (Labour charges for plumber for removing the existing water supply PVC lines on the terrace during waterproofing work and refitting them after completion, including all required materials, complete.)	Job	1.0	5,750.0	18.0	6,785.0
10	Providing and Fixing New G.I. Gutter (8" Wide) (Providing and fixing new G.I. gutter of 8-inch width with proper slope and connecting drain pipe at suitable locations for the existing covered dining area shed at ground floor, complete.)	RMT	12.5	630.0	18.0	9,292.5
11	Providing and Fixing 0.5 mm Galvalume Sheet Roofing (Providing and fixing 0.5 mm thick Galvalume sheet of approved brand (Jindal, Tata, or equivalent) over the supporting structure of drinking water counter and hand wash counter, fixed with J-bolts, nuts, washers, and other required accessories, complete.)	Sq	405.0	1,675.0	18.0	8,00,482.5
			Quotation Value			15,61,691.0
Payment Terms		70% Advance with the work order balance after completion of work.				
Freight		N.A.				
Installation		N.A				
Delivery Schedule		45 Days.				
Warranty/Guarantee		180 Days.				
General Remarks		Water and power supply free of cost from your side on site.				

Print Date/Time: 2025-12-20/16:45:43