

ENQUIRY DETAILS	
Enquiry No	UWB/2025-26/CSR/060
Enquiry Date	2025-12-18
Enquiry Particulars	250 LPH Water ATM in 6 Village of Halol
Indent No	87
Indent Date	2025-12-11
Project No	UWB/2025-26/CSR/033
Project Date	2025-12-11
Project Type	CSR
Project Name	Sun Pharma water ATM Halol
Project Coordinators	Nikul Davda, Mrugesh Patel, Vipul Parmar
Submission By	2025-12-20 21:00:00

Srl	Item Particulars	UOM	Qty
1	250 LPH RO Unit with 3-year AMC • Capacity: 250 LPH • ISI Marked, ISO Certified • FSSAI & BIS Approved Kent / Eureka Forbes / Blue Star / AquaSure / Livpure / Zero B / Netsol Water Or Equivalent Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
2	2 Ton Chiller • Steel frame, copper condenser & evaporator • Corrosion-resistant & permitted material • Eco-friendly refrigerant • Certifications: ISI, CE, NSF Blue Star / Voltas / Celfrost / Western / Usha Or Equivalent Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
3	Water Purifier Storage Tank (1000 Liter) • Triple-layer, food-grade polymer • Anti-bacterial (silver-ion coating) 3 Layer Antimicrobial • With MS stand support Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
4	GSM Base Coin Panel (1 Pair) • ISI Marked, Standard Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
5	Earthing and all necessary electrical fitting • Anchor Cables, MCB, Switchboards (ISI Marked) • Complete earthing & wiring Standard ISI Approved Or Equivalent Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
6	Raw Water Storage Tank (2000 Ltr.) • Triple-layer, food-grade polymer • Anti-bacterial (silver-ion coating) 3 Layer Antimicrobial Raw Water Storage Tank (2000 Ltr.) Certified Food Grade and Anti-Microbial Storage Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	5.00
7	Fully automatization Plant • Lubi Motors • SV Valves • Finolex UPVC Pipes Lubi / Finolex / Equivalent Or Equivalent Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
8	CCTV Camera (HD) • 2 MP HD Resolution • Night Vision, Bullet Camera • SIM-based operation Canon / Dahua / CP Plus / Ahuja / Samsung / Hikvision Or Equivalent Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
9	Civil Work Construction 12' x 12' plinth platform for prefab shed (c/o) upto plinth level. as per drawing. Height of the platform 2' above surrounding ground level. Proper drainage system with outlet. Separate pedestal of 1600 mm dia Ghoghamba, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), and Panelav,	Nos	4.00
10	Civil Work Construction 12' x 12' plinth platform for prefab shed (c/o) upto plinth level. as per drawing. Height of the platform 2' above surrounding ground level. Proper drainage system with outlet. Separate pedestal of 1600 mm dia with proper RCC work Tajpura	Nos	1.00
11	Comprehensive Maintenance Contract (CMC) • 2 Years (after 1-year brand warranty) Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
12	Cabinet Unit for Water ATM Machinery • Dimensions: 12' x 12' • 50 mm PUF insulated cabinet • Door size: 6' x 3' Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00

Srl	Item Particulars	UOM	Qty
13	Monitoring & Evaluation (Monthly Monitoring Report, Key Outputs and other associated details will be shared regularly)Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
14	Transport, Installation, TrainingGhoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
15	automatization of borewell with wire and necessary things, and plumbing of water supply line and waste water line chargesTajpura	Job	1.00
16	Bore Well 180 Ft with 1.5 HP Pump Motor • Pump: 1.5 HP (Lubi or equivalent) Water supply line from borewell to the overhead water tank may be included in this item (pipes of Supreme, Astral etc.) Lubi / EquivalentPANELAV	Job	1.00
17	Fixing of 1.5 HP borwell motor pump, with pipe, starter • Pump: 1.5 HP (Lubi or equivalent) Water supply line from borewell to the overhead water tank may be included in this item (pipes of Supreme, Astral etc.) Lubi / Equivalent • wire and its automatization and plumbing of water supply line and waste water line with inlet pipe of 90 RFT and outlet 20 RFTPRATAPURA (BILIYAPURA)	Job	1.00
18	Fixing of 1.5 HP submersible motor pump, with pipe, starter • Pump: 1.5 HP (Lubi or equivalent) Water supply line from borewell to the overhead water tank may be included in this item (pipes of Supreme, Astral etc.) Lubi / Equivalent • wire and its automatization and plumbing of water supply linePRATAPURA (RINKI CHOKDI)	Job	1.00
19	Fixing of 1.5 HP borwell motor pump, with pipe, starter and wire and its automatization and plumbing for raw water and waste water line connection to drainage line with inlet pipe 50 RFT and Outlet 70 RFTSHIVARJPUR	Job	1.00
20	Fixing of 1.5 HP borwell motor pump, with pipe, starter Pump: 1.5 HP (Lubi or equivalent) Water supply line from borewell to the overhead water tank may be included in this item (pipes of Supreme, Astral etc.) Lubi / Equivalent and wire and its automatizationGHOGHAMBAA	Job	1.00
21	Drainage line work for waste water 15 feetGHOGHAMBAA	Job	1.00
22	Paver block 15*9 feet with 3.5 CUM land filling, cleaning of areaPRATAPURA (RINKI CHOKDI)	Job	1.00
23	Civil work : Concrete pile base for 2000 ltr water tankSHIVARJPUR	Job	1.00
24	Sim cards with 3 Years of Data Plan Ghoghamba, Shivrajpur, Pratapura (Rinki Chokdi), Pratapura (Biliyapura), Panelav, and Tajpura	Nos	6.00
<b>Print Date/Time: 2025-12-18/13:13:03</b>			

**Prepared By: Nikul Davda**

